

HOLIDAY INN HOTELS SPECIFICATIONS
SECTION 06615
CAST MARBLE FABRICATIONS

PART 1 – GENERAL

1.1 SUMMARY

- A. The following products are to be cast marble:
 - 1. Shower bases as required
 - 2. Tub & shower surrounds; related accessories.
 - 3. Window sills

- B. Related sections:
 - 1. Section 06100 – Rough Carpentry.
 - 2. Section 06400 – Architectural Woodwork.
 - 3. Section 07900 – Joint Sealers.
 - 4. Section 09250 – Gypsum Board Systems.
 - 5. Section 09300 – Tile: Shower floor and base.
 - 6. Section 15400 – Plumbing.

1.2 REFERENCES

- A. Standards of the following as referenced:
 - 1. American National Standards Institute (ANSI).
 - 2. International Cast Polymer Association (ICPA).
 - 3. Environmental Protection Agency (EPA).
 - 4. National Association of Home Builders, Research Foundation, Inc. (NAHB/RF).

1.3 DEFINITIONS

- A. Terms:
 - 1. Cast Marble: Cast Polymer, Cultured Marble, Synthetic Marble; synonymous terms.
 - 2. Contractor: General Contractor and/or its employees.
 - 3. Manufacturer: Cast Marble Manufacturing Company.
 - 4. Installer: Cast Marble Installation Company.

- B. Description:
 - 1. A non-porous homogeneous mixture of natural minerals and polyester resins thermally bonded to produce solid fabrications with sealed surfaces.

1.4 SUBMITTALS

- A. Shop Drawings:
 - 1. Submit top views, elevations and sections (as needed). Indicate dimensions, material thickness, location and sizes of cutouts, anchorage provisions and attachment methods. Indicate coordination requirements with adjacent and interfacing work.

- B. Color: #2250 Solid White/Gloss by Mincey Marble Mfg., Inc.

- C. Samples:
 - 1. Submit tub/shower samples of TS-ST 8 x 8 Simulated Tile for approval by architect.

- D. Product Data:
 - 1. Submit manufacturer's product data indicating compliance with specified performance requirements.

2. Operation and maintenance data. Manufacturer's data indicating cleaning and maintenance requirements.
3. Quality Assurance submittals as needed to comply with Section 1.5.

1.5 QUALITY ASSURANCE

A. Qualifications:

1. Cast marble manufacturer qualifications:
 - a. ICPA member one calendar year, minimum, prior to Contract date.
 - b. Five years experience, minimum, in manufacturing similar type units.
 - c. Fabricated five Projects, minimum, of comparable magnitude in last three years.
 - d. Architect reserves right to inspect fabricator's facilities in determining acceptability of cast marble work.
 - e. Approved by Architect prior to contract signing.
2. Installer qualifications:
 - a. Installed five Projects, minimum, of comparable magnitude in last three years. Provide reference list of those completed Projects for review and verification.
 - b. Approved by Architect prior to signing of Contract.

B. Performance Requirements: Cast marble products are to comply with the following standards:

1. Vanity tops – Tested by NAHB Research Center, Upper Marlboro, MD.
ANSI Z-124.3, 1995; Plastic Lavatory Units.
BOCA 1206.2/CABO 2314.1; Lavatory Waste Outlet Dimension.
SBCCI 902; Overflow Requirements.
2. Shower Bases – Tested by NAHB Research Center, Upper Marlboro, MD.
ANSI Z-124.2, 1995; Shower Receptors.
BOCA 1216.3, 1216.4, 1216.5; Dimensional Requirements.
CABO 2309.1, 2310.1; Dimensional Requirements.
SBCCI 910.1, 923.2; Dimensional Requirements.
UPC 410; Dimensional Requirements.

1.6 DELIVERY, STORAGE AND HANDLING

A. Packing and shipping:

1. Vanity tops, tub surrounds and other flat products to be packed in wooden crates to minimize damage in shipping. Undermount china bowls to be palletized.

B. Acceptance at site:

1. Contractor or Installer to supervise unloading of materials. A forklift is required. Check for damaged crates. Mark bill of lading if there is any obvious damage and notify marble supplier immediately. Otherwise, proceed with offloading crates.

C. Storage and protection:

1. Store materials under shelter, off of ground, protect from moisture. Material are to be at room temperature prior to installation. Handle materials to prevent physical damage. Protect surfaces from staining, scratching and other damage during handling.

1.7 PROJECT CONDITIONS

A. Field measurements:

1. Shop drawings are to be field verified by Contractor to ensure proper fit of materials prior to fabrication.

1.8 WARRANTY

- ### **A. Manufacturer's standard five year limited warranty on defective materials.**

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Acceptable Manufacturer: Mincey Marble Manufacturing, Inc.; 4321 Browns Bridge Road, Gainesville, GA 30504. Tel: 770.532.0451 or 800-533-1806. Fax: 770-531-0935.
- B. Requests for substitutions will be considered in accordance with provisions of Section 01600.

2.2 SURROUNDS

- A. Tub and shower surrounds: TS-ST 8" x 8" Simulated Tile - subject to compliance with requirements:
 - 1. ¼" thick cast synthetic marble wall panels. Panels are to extend to the ceiling.
 - 2. Tub and shower surround back panels to be one piece.
 - 3. Provide required integral bullnose trim.
 - 4. For typical units, provide 2 ceramic corner mount soapdishes. For accessible baths, provide 1 soap dish 6-9/16" x 3-5/8" without washcloth holder down low and 1 ceramic corner soap dish.
- B. Adhesives and sealants:
 - 1. To adhere panels to gypsum board use:
 - a. LN-933 Liquid Nails.
 - b. Nail-No-More.
 - c. Or other as acceptable to Architect.
 - 2. To seal interior seams (marble to marble) a 100% mildew resistant silicone is required.
 - a. Shurstik – 100% Silicone Caulk (Gibson-Homans).
 - b. Dow Corning Corp., #786 Mildew Resistant Silicone Sealant.
 - c. Or other as acceptable to Architect.
 - d. Siliconized caulk is NOT acceptable.**
 - 3. To caulk marble panels to adjoining gypsum board, wallpaper or paint, use mildew resistant acrylic caulk sealant:
 - a. Phenoseal Acrylic Caulk (Gibson-Homans).
 - b. Or other as acceptable to Architect.

PART 3 – EXECUTION

3.1 INSTALLATION - GENERAL

- A. Install components in accordance with reviewed shop drawings and plans.
- B. All materials to be plumb, level and rigid. Neatly scribe to adjoining surfaces.
- C. Field trim all components as needed to fit field conditions.
- D. Immediately replace any material that is cracked, chipped, broken or otherwise defective.

3.2 INSTALLATION – TUB SURROUNDS

- A. Provide cutouts in panels as required for the installation of plumbing outlets.
- B. Secure soap dishes to panels per manufacturer's written instructions.

3.3 CLEANING

- A. Contractor to protect all finished work until final acceptance by Owner.
- B. Clean installed units not more than 48 hours prior to Date of Substantial Completion. Repair or replace damaged or stained cast marble work.

END OF SECTION 06615